



PAT320

PAT350

PAT410

PAT420

PAT450

SUPPLY					
230V	■	■	■	■	■
110V	■	■		■	■
Supply measurement	■	■	■	■	■
EARTH BOND/CONTINUITY					
200mA	■	■	■	■	■
10A	■	■		■	■
25A	■	■		■	■
Bond Lead Null	■	■	■	■	■
INSULATION TEST					
250V	■	■	■	■	■
500V	■	■	■	■	■
FLASH TEST					
1.5kV and 3kV		■			■
ALTERNATIVE LEAKAGE TESTS					
Substitute	■	■	■	■	■
Differential	■	■	■	■	■
Touch current	■	■	■	■	■
OPERATION TEST					
VA Measurement	■	■	■	■	■
EXTENSION LEAD TESTS					
Earth Bond	■	■	■	■	■
Insulation	■	■	■	■	■
Polarity	■	■	■	■	■
Portable RCD tests	●	■	■	■	■
OTHER FEATURES					
Low-profile light weight			■		
Auto test routine	■	■	■	■	■
Manual testing	■	■	■	■	■
Fuse Check	■	■	■	■	■
Colour display	■	■	■	■	■
110V test connection	■	■		■	■
Configurable tests times	■	■	■	■	■
Selectable pass limits	■	■	■	■	■
Lead storage pouch	■	■	■	■	■
10,000 record on-board storage			■	■	■
Download to USB Memory Stick			■	■	■
PowerSuite compatible			■	■	■